BRUHAT BANGALORE MAHANAGARA PALIKE

3BMP/2014-15/OW/WORK_INDENT14346/CALL-

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/10/2014-15, Date: 21.02.2015

Construcion and Repair of Anganavadi Building in Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M B HOMBAL	
				In Figures	In Words
1	23.28	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD SR 2014-15	Cum	146.88	Rupees One Hundred Forty Six and Eighty Eight Paise Only
2	104.79	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.3/ PWD SR 2014-15	Cum	264.6	Rupees Two Hundred Sixty Four and Sixty Paise Only
3	13.51	KSRB 2.8 : Providing and filling in foundation with granite/trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, complete as per specifications. Specification. No. KBS, No. 6/ Item No. 2.15/ PWD SR 2014-15	Cum	1962.36	Rupees One Thousand Nine Hundred Sixty Two and Thirty Six Paise Only
4	19.45	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M10 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2014-15	Cum	4847.04	Rupees Four Thousand Eight Hundred Forty Seven and Four Paise Only
5	18.73	KSRB 5.3-1 Providing and constructing granite / trap / basalt size stone masonry in basement with mud mortar, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2014-15	Cum	4542.48	Rupees Four Thousand Five Hundred Forty Two and Forty Eight Paise Only
6	58.22	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. No. KBS 2.9, No. 6/ Item No. 2.10/ PWD SR 2014-15	Cum	118.8	Rupees One Hundred Eighteen and Eighty Paise Only

7	38.8	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2014-15	Cum	6065.28	Rupees Six Thousand Sixty Five and Twenty Eight Paise Only
8	36.62	KSRB 6-2.3 Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2, Page No. 27/ Item No. 6.6/ PWD SR 2014-15	Cum	6308.28	Rupees Six Thousand Three Hundred Eight and Twenty Eight Paise Only
9	22.59	KSRB 9-18.1: Providing and fixing in position Honne wood fully panelled shutters for windows with styles and rails of 25mm. thick, 75mm wide in two halves with panels of 20mm thick including cost of materials, labour charges, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No.9.34. Page No. 55/ Item No. 9.52/ PWD SR 2014-15	Sqm	3972.24	Rupees Three Thousand Nine Hundred Seventy Two and Twenty Four Paise Only
10	3.15	"SOLID PVC DOOR FRAMEProviding & fixing factory made PVC Door frame of size 50x47 mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2No.s of 150mm long brackets of 15x15 mm M.S. Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufactures specification & direction of Engineer-in charge Page No. 57/ Item No. 9.84/ PWD SR 2011-12	Sqm	560.52	Rupees Five Hundred Sixty and Fifty Two Paise Only
11	1.58	SOLID PANEL PRELAM PVC DOOR SHUTTERProviding & fixing 30mm thick factory made rigid foam prelam panelled Door Shutters made from M.S. tube of 19x19mm, 19 gauge for styles and 15x15mm for top & bottom rails, covered with heat moulded prelaminated PVC 'C' Channel of 5mm thick sheet & 30x50mm wide of form styles & 5mm thick & 75mm wide prelaminated PVC sheets for top rail, lock rail & bottom rail on either side & 5mm thick, 20mm wide cross PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet Prelaminated on either side fitted in the M.S. frame, sealed to the styles &rails with PVC designer beading on either side & joined together with solvent cement adhesive etc., complete as per manufactures specification & direction of Engineer –in-charge fixed to frames with 3nos of 75mm. Aluminium hinges. Page No. 58/ Item No. 9.85/ PWD SR 2014-15	Sqm	4276.8	Rupees Four Thousand Two Hundred Seventy Six and Eighty Paise Only
12	101.31	KSRB 15.3.13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications Page No. 110/ Item No. 15.21 PWD SR 2014-15	Sqm	186.84	Rupees One Hundred Eighty Six and Eighty Four Paise Only

13	383.87	KSRB 15-3.7:- Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.15/ PWD SR 2014-15	Sqm	237.6	Rupees Two Hundred Thirty Seven and Sixty Paise Only
14	25.92	KSRB 15.3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 110/ Item No. 15.18 / PWD SR 2014-15	Sqm	253.8	Rupees Two Hundred Fifty Three and Eighty Paise Only
15	25.92	KSRB 15.4.1 : Extra for providing and mixing water proofing compound in cement plaster work at one kg per bag or in the proportion recommended by the manufactures, for cement mortar 1:3, 12mm thick cost of materials complete as per specifications. Page No. 110/ Item No. 15.23/ PWD SR 2014-15	Sqm	9.18	Rupees Nine and Eighteen Paise Only
16	3.88	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2014-15	Qtl	78351.84	Rupees Seventy Eight Thousand Three Hundred Fifty One and Eighty Four Paise Only
17	113.1	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15/ Item No. 4.29.2/ PWD SR 2014-15	Sqm	572.4	Rupees Five Hundred Seventy Two and Forty Paise Only
18	113.1	KSRB 4-6.10 : Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.37/ PWD SR 2014-15	Sqm	270.0	Rupees Two Hundred Seventy Only
19	485.18	KSRB 15.7: Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. Page No. 110/ Item No. 15.17/ PWD SR 2014-15	Sqm	189.0	Rupees One Hundred Eighty Nine Only
20	446.44	KSRB 15-3.7:- Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.15/ PWD SR 2014-15	Sqm	237.6	Rupees Two Hundred Thirty Seven and Sixty Paise Only
21	485.18	KSRB 15.15.3: Providing and applying painting in one coat with plastic emulsion paint of approved brand and manufacture on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, complete as per specifications. Page No.114/ Item No. 15.52 / PWD SR 2014-15	Sqm	43.2	Rupees Forty Three and Twenty Paise Only

22	3	Providing and fixing Ceramic tiles of size 400x400mm for flooring, threads,steps and landing,laid on a bed of 20mm thick cement morta. 1:3 mix flush pointing with white cement mixed with matching colour pigment including curing, clearing etc. complete .The Worked including curing., clearing etc., complete, The work includes cost of all materials. Labour charges for all items or work, hire charges for equipment, etc., complete as per specification. Page No. 116/ Item No. 14.63 / PWD SR 2014-15	Sqm	1082.16	Rupees One Thousand Eighty Two and Sixteen Paise Only
23	17.85	KSRB 14.17.2: Providing skirting, dado, rises of steps with Colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface white should be measured and paid separately) using glazed tiles of approved make and size of materials, labour, complete as per specifications. Specification No. KBS 14.17. Page No. 103/ Item No. 14.41.1 / PWD SR 2014-15	Sqm	1017.36	Rupees One Thousand Seventeen and Thirty Six Paise Only
24	446.44	SKSRB 15-16 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. Page No. 114/ Item No. 15.53.2 / PWD SR 2014-15	Sqm	81.0	Rupees Eighty One Only
25	101.31	Providing and fixing Special make glazed Vitrified tiles (Granomite finis) of approved make, quality and colour of sized 6000x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete. Page No. 104/ Item No. 14.43 / PWD SR 2014-15	Sqm	1212.84	Rupees One Thousand Two Hundred Twelve and Eighty Four Paise Only
26	21.6	KSRB 15.17.8 : Extra over item No. 15-17.6 for applying every subsequent coat of enamel paint to give an even shade after cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. Page No.113/ Item No. 15.60.2 / PWD SR 20114-15	Cum	48.6	Rupees Forty Eight and Sixty Paise Only
27	14	90mm pipe outer dia(3 layer) Page No. 95 /Item No. 13.95.8 PWD SR 2014-15	Mtr	1371.6	Rupees One Thousand Three Hundred Seventy One and Sixty Paise
28	64	Providing and fixing chlorinated poly veny chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing, this including jointing of pipes and fittings with one step CPVC solvent cement and the cost of cutting chases & making good the same including testing of joints complete.(concealed work including cutting chases and good the walls etc,),15mm nominal OD pipes Page No. 92/ Item No. 13.83.1/ PWD SR 2014-15	Mtr	270.0	Rupees Two Hundred Seventy Only
29	1000	Supppying water storage tanks made of virgin polymer (LLDPE) with two layers outer black of blue and inner white layer of approved quality and make, conforming to ISI / ISO / SSI specifications, No. 252/ Item No. 37.58 PWD SR 2014-15	Mtr	6.48	Rupees Six and Forty Eight Paise Only
30	4	KSRB 13-6.1.2 : Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification NO. KBS 13.2.2 / 13.3, Page No. 88/ Item No. 13.24 / PWD SR 2014-15	Each	260.28	Rupees Two Hundred Sixty and Twenty Eight Paise Only

31	2	Orissa Pattern of size 575x425mm with integral type footrests	Each	1026.0	Rupees One Thousand Twenty Six Only
32	52.2	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shutterng machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Matirial (DATA RATE ENCLOSED) 10cm thick RCC pre cast slab	Sqm	1856.67	Rupees One Thousand Eight Hundred Fifty Six and Sixty Seven Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92